F. Paving inspections

1. Subgrade inspection:

   After subgrade has been established, tested and approved by the geotechnical engineer or his qualified representative. The geotechnical engineer shall provide a field memo of compaction test results. The civil engineer shall provide a field memo that line and grade is set in accordance with approved plans.

2. Untreated base inspection:

   After untreated base course has been placed, tested and approved by the geotechnical engineer or his qualified representative, but prior to asphalt placement. The geotechnical engineer shall provide a field memo of compaction test results. The civil engineer shall provide a field memo that line and grade is set in accordance with the approved plans. Material invoices may be required.

3. Asphalt inspections:

   a. During asphalt lay down to verify continuous inspection by the geotechnical engineer or his qualified representative or a Special Inspector when authorized. Material invoices may be required.

   b. Prior to application of seal coat, the paved surface shall be water tested to reveal any irregularities and shall be patched where required. Material invoices may be required after placement of seal coat.

   c. Deputy Inspector is not required at asphalt concrete plant.